BRUHAT BANGALORE MAHANAGARA PALIKE

ind Venugopalswamy temple in ward no. 10 (Doc

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/07/2014-15, Date: 31.10.2014

construction of 3 Bus stops in ward no. 10 (Doddabommasandra), Vidyaraynapura sub division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of K V SUBBA REDDY	
				In Figures	In Words
1	122.47	Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m , in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. etc	Cum	234.8	Rupees Two Hundred Thirty Four and Eighty Paise Only
2	16.61	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180 Kgs using 40mm and down size graded granite metal, corse aggregates @ 0.85 cum and fine aggregtes @ 0.58cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4421.11	Rupees Four Thousand Four Hundred Twenty One and Eleven Paise Only
3	27.68	Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammered dressed in courses not less than 20 cms high, bond stones, at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	3657.73	Rupees Three Thousand Six Hundred Fifty Seven and Seventy Three Paise Only
4	14.81	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stone chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4355.45	Rupees Four Thousand Three Hundred Fifty Five and Forty Five Paise Only
5	167.38	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	Sqm	231.46	Rupees Two Hundred Thirty One and Forty Six Paise Only
6	123.33	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	Sqm	298.23	Rupees Two Hundred Ninety Eight and Twenty Three Paise Only
7	42.84	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1.5:3) for raft foundation, column footing, main and secondary beams. etc complete as per specifications and directions of engineer in charge of the work	Cum	6661.15	Rupees Six Thousand Six Hundred Sixty One and Fifteen Paise Only

8	53.55	Providing Mild steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery etc complete as per specifications and directions of engineer in charge of the work	Qtl	7677.12	Rupees Seven Thousand Six Hundred Seventy Seven and Twelve Paise Only
9	22.91	Providing and constructing burnt brick masonry with approved quality of modular bricks of standard size of class designation 50 (table moulded) with cement mortar 1:6 for basement and superstructure including cost of materials, labour charges, scaffolding, etc complete as per specifications and directions of engineer in charge of the work	Cum	6078.05	Rupees Six Thousand Seventy Eight and Five Paise Only
10	111.6	Providing and laying integral cement based waterproofing treatment including preparation of surface as required for treatment of roofs, balconies, terraces etc, consisting of following application. (a) Applying and grouting a slurry coat of neat cement using 2.75kg/sqm conforming admixed with proprietary water proofing compound conforming to IS:2645 over the RCC slab after cleaning the surface before treatment, (b) laying cement concrete using broken brick bats 25mm to 100mm size with 50% of cement mortar 1:5 admixed with proprietary water proofing compound conforming IS:2645 over 20mm thick layer of cement layer of cement mortar 1:5 admixed with proprietary water proofing compound to required slope and treating similarly the adjoining walls upto 300mm height including rounding off junction of walls and slabs, (c) after two days of proper curing, applying a second coat of cement lurry admixed with proprietary water proofing compound (d) Finishing the surface with 20mm thick jointless cement mortar of mix 1:4 admixed with proprietary water proofing compound and finally finishing the surface with trowel and neat cement	Sqm	817.9	Rupees Eight Hundred Seventeen and Ninety Paise Only
11	99.81	Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	171.37	Rupees One Hundred Seventy One and Thirty Seven Paise Only
12	98.28	Providing 20mm thick cement plaster in single coat with cement mortar 1:4, to stone masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	209.2	Rupees Two Hundred Nine and Twenty Paise Only
13	198.09	Providing lime rendering for plastering to wall and ceiling, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	20.03	Rupees Twenty and Three Paise Only
14	102.36	Providing 18mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	173.59	Rupees One Hundred Seventy Three and Fifty Nine Paise Only
15	22.11	Providing & fixing Granite Seating with necessary fitings etc complete and as per directions of Engineer-In-Charge.	Sqm	3684.8	Rupees Three Thousand Six Hundred Eighty Four and Eighty

16	19.09	Providing and laying in position plain cement concrete of mix M15 with cement @ 240 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4924.09	Rupees Four Thousand Nine Hundred Twenty Four and Nine Paise Only
17	104.73	Providing and laying flooring using pre polishing water cut/gang saw 19 mm thick Granite slab over existing cement concrete bed in CM 1:4 average 20mm thick pointed with white cement / colour pigment etc., complete. using grey granite etc complete as per specifications and directions of engineer in charge of the work	Sqm	2169.94	Rupees Two Thousand One Hundred Sixty Nine and Ninety Four Paise Only
18	54	Providing and fixing of wall cladding using 20mm thick gang saw water cut Shiva gold granite, grey granite in CM 1:3 proportion cut to required shape, pattern with paper joints, finished with cement mortal using white cement and colour pigments to match the colour of slab making through jointing with sealant, making holes 25mmx12mm grooves in joints including curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	4542.4	Rupees Four Thousand Five Hundred Forty Two and Forty Paise Only
19	111.6	Providing and laying in position yelahanka tiles of size 250x250mm of approved quality and make, over a bed of cement mortar 1:3 an average thickness 25mm over weather proof course and pointed with cement mortar 1:3 mix with red oxide including curing cost of materials, labour etc complete as per specifications and directions of engineer in charge of the work	Sqm	706.62	Rupees Seven Hundred Six and Sixty Two Paise Only
20	198.09	Providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper primer after thoroughly brooming the surface free from mortar drops and other foregin matter including preparing the surface even and sand paper smooth, cost of materials, labours, etc complete as per specifications and directions of engineer in charge of the work	Sqm	62.32	Rupees Sixty Two and Thirty Two Paise Only
21	102.36	Providing and finishing external walls in tow coats with water proof cement paint of approve brand and shade to give an even shade after thourghly brooming the surface to remove all dirt and losse powdered material, free from mortar dops and other foreign matter cost of materials, labours, with Primer etc complete as per specifications and directions of engineer in charge of the work	Cum	82.35	Rupees Eighty Two and Thirty Five Paise Only

R.V. Subba Reddy

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92